



Subject: Notice Inviting Bids for the Lake Arrowhead Community Services
District DLP-LACSD Emergency Waterline Interconnection, Project No. 164

Sealed bids will be received at the Engineering Department of the Lake Arrowhead Community Services District (District), located at 27307 State Hwy 189, Blue Jay, California, until 2:00 p.m. on March 28, 2019 for this project. The bids will be publicly read shortly after 2:00 p.m. on March 28, 2019. There will be a MANDATORY job walk at 10:00 a.m. on March 20, 2019. All interested Contractors shall meet at the District Offices at, 27307 State Hwy 189, Blue Jay, CA, at 10:00 a.m. prior to the start of the conference. The work consists of providing all materials, labor, tools, equipment, facilities, transportation and incidentals necessary to construct: One Reduced Pressure Principal Assembly (RPPA) Vault. Work will include one Jensen precast SPCL 6.5 X 5 X 7 TFC vault with heavy duty traffic galvanized hinged lid spring assisted, joint sealant, and 2-piece or approved equal (to be supplied by the Contractor). This vault will contain a 6" Wilkins RPPA Model 375 (to be supplied by the District). This vault will be installed underground, and it will drain to daylight within a slope. The assembly shall be mounted at a minimum of 12" (305mm) and a maximum of 30" (762mm) above adequate drains with sufficient side clearance (2.58') for testing and maintenance. The installation shall be made so that no part of the unit can be submerged. The vault, all appurtenances to connect to existing 6" PVC water main, 4" drain with grate assembly, piping, and pipe supports shall be supplied and installed by the Contractor. One Meter/ PSV vault will include one Jensen precast SPCL 5X8X7 TFC vault with heavy duty traffic galvanized hinged with spring assisted, joint sealant, and 2-piece or approved equal (to be supplied by the Contractor) This vault will contain one 6" Zenner Meter Model PFS04X4 (to be supplied by the District) and one 6" pressure Sustaining Valve CLA-VAL Model 50-90 (to be supplied by the District). The vault, all appurtenances to connect to existing 6" PVC water main, piping, and pipe supports shall be supplied and installed by the Contractor. The site of the work is located in: Lake Arrowhead, California. The site address is: On Evergreen Lane between Arrowhead Woods and Deer Lodge Park

The Engineers Estimate for this project is \$65,000.

Copies of the plans, specifications and all bid documents are to be obtained from the Lake Arrowhead Community Services District, Engineering Department, 27307 State Hwy, Blue Jay, CA 92317, Telephone (909) 336-7106. Specifications will be available to each bidder at a cost of \$20.00 for each set. Each set can be shipped via FedEx Ground, upon request, for an additional \$10.00 charge each to cover shipping and handling. Or you may provide your own FedEx account number.

Published in the Mountain News March 14, 2019.